



128633

RECORDED
HILLSDALE CO. MICH.

'97 NOV 24 PM 2 51

LIBER 3 PAGE 221

**HILLSDALE COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Jessie VanZandt
REG. OF DEEDS
**SURVEY &
REMONUMENTATION**
FEB 11 1998
SECTION
Register of Deeds Stamp & File Number

For corners in

<u>HILLSDALE</u>	Located In:	Corner Code #
(County)		
CAMBRIA TWP.		
1. Public Land Survey	<u>T 7 S R 3 W</u>	<u>E-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on NOVEMBER 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
CORNER COMMON TO SECTIONS 8-9-16-17, CAMBRIA TWP.

1977: E.R. REED, SURVEYOR - RE-ESTABLISHED CORNER FROM PLAT OF NORTH SAND DUNES AS RECORDED, SET 4" DIA. HARRISON MARKER AND RECORDED IN LCRC FORMS IN HILLSDALE COUNTY REGISTER'S OF DEEDS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND HARRISON MARKER AS WITNESSED

SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" IRON ROD IN CI-MONUMENT BOX

12" WALNUT, S 43 W 73.25 TO CENTER
POWER POLE, S 19 E 46.9' TO NEAR FACE
POWER POLE, N 15 E 99.6' TO NEAR FACE
WOOD ANCHOR POST, N 73 E 35.4' TO NEAR FACE
CONC. PLAT MONUMENT, WEST 33.0'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*
EDWARD W. REED

Date NOVEMBER 14, 1997

Surveyor's Michigan License No. 33985

