

**SURVEY &
REMONUMENTATION**

1993

LIBER 3 PAGE 29

COMMISSION

REMONUMENTATION

88379

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
HILLSDALE CO. MICH.
'93 DEC 27 PM 3 38

John E. Maxson
REG. OF DEEDS

For corners in

HILLSDALE
(County)

Located In:

Corner Code: #

		7S	3W	
1. Public Land Survey	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
2. Property Controlling in Section	S	_____	T	_____
	S	_____	T	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____
	S	_____	T	_____

G-1, I-1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John E. Maxson, on 27 December, 1993, in a field survey on _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1	I-1
GLO, 1823, 30 Oak, S64W, 59 lks	GLO, 1823, 24 Elm, S08E, 17 lks
22 Sugar, S32E, 114 lks	14 Beech, S31W, 40 lks
LCRC, 1988, Ringenberg, L575, P214	
Rebar	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1	I-1
Found iron from Ringenberg LCRC and accepted as the best available evidence of the position of the original Corner	Found Iron at record offset and accepted as the best available evidence of the position of the original Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1	I-1
reset 5/8 x 36 rebar with cap	reset 5/8 x 36 rebar with cap
N10E 18.00' 15"Maple	South 12.97' 20"Maple
N05W 14.76' 15"Maple	East 17.80' 18"Tree
S25E 43.68' 30"D.Maple	West 52.67' P.Pole
S25W 40.50' 24"Maple	East 3.81' Fence Post
West 53.46' G-13 @ T6S-R3W	West 64.68' I-13 @ T6S-R3W



Signed by *John E. Maxson*
Surveyor's Michigan License No. 27454

Date 27 December, 1993