

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1967 AT A MEETING HELD ON [Signature] AL RINGENBERG, CO. REC.

LIBER 3 PAGE 215 HILLSDALE REMONUMENTATION

RECORDED HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

97 NOV 12 AM 9 07

For corners in

Table with columns: Hillsdale (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Handwritten signature: Jerry VanZandt

SURVEY & REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number

SECTION

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column H and row 4.

Frederick J. Cutcher

I, Cutcher, in a field survey on 11/8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey by William Brookfield, 1825: W. Wood 28" S. 2° 5' E. 45 lks.; Beech 12" S. 74 1/2° E. 34 lks.

LCRC, 10/16/73, A.J. Hatt (records of Ringenberg, unrecorded): Set R.R. spike; Stone by cor. fnc. post N. 45° E. 46.10'; Rd. sign post N. 50° E. 47.65'; Nail S.W. side pwr. pole S. 30° E. 63.58'.

LCRC L. 553, P. 455, Bruce Leone, 9/13/86: Fd. R.R. spike from above witnesses & set Harrison monument in pavement; P.K. nail N.E. side pwr. pole N. 59° W. 67.22'; P.K. nail N.E. side twin 4" Maple N. 39° W. 48.88'; P.K. nail N.W. side pwr. pole N. 26 1/2° E. 98.07'; Rd. sign post N. 69° E. 53.48'; Hatt's nail N.E. side pwr. pole S. 28° E. 63.50'.\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

\*This corner was recovered by J.E. Maxson in August, 1995, and prior to paving of Hillsdale Road a monument box was set by contractor.

On 9-16-97 I found a monument box with no iron.

Four witnesses were found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On 11-8-97 I dug down in monument box and found it filled with asphalt 17" below road surface. Set 1/2"x18" iron with County remonumentation cap in center of monument box and is accepted as best available evidence of the position of the original corner.

1.9' West of centerline Hillsdale Road. In centerline Bear Lake Road. Nail & spotter West side pwr. pole S. 28° E. 63.50' Fd. P.K. N.W. side pwr. pole N. 26 1/2° E. 98.14' Fd. P.K. N.E. side pwr. pole N. 59° W. 67.34' N.W. cor. tel. stan. S. 50° W. 52.60'

Signed by Frederick J. Cutcher Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date 11/10/97

