

**SURVEY &  
REMONUMENTATION**

LIBER 3 PAGE 5

DEC 15 1993

87704

RECORDED  
HILLSDALE CO. MICH.

'93 DEC 8 AM 8 47

**COMMISSION REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

*Judy VanZandt*  
REG. OF DEEDS

For corners in

<u>Hillsdale</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T 7S R 4W T 7S R 4W T R T R	<u>E-3</u> F-3
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

Register of Deeds Stamp & File Number

4. Lot.No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R. Timothy Tietsema, in a field survey on November 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-3)  
1823-GLO: Set original corner.  
9/8/1887-George A. Marks (Co. Surveyor) L VII, P 367  
Set Stone, Stake and Brick

F-3)  
1823-GLO: Set Original Corner.  
  
12/29/1975-R.E. Burris, Sr. LS#19563: Set R. R. Spike in line w/the SW Cor. and SE Cor. of Sec. 4 at the midpoint.  
12" Maple S05E 42.78'  
24" Oak S77W 92.21'

Allen Ringenberg Records (unknown date): set 1/2" Iron in proportional measurement to South and set from Steven's Landing Plat, Liber 3, Page 41, H.C.R.  
Cross in Bridge S80W 32.93'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3)  
Found 1/2" Iron Rod from the following:  
Sw Corner of SE Wing Wall of Bridge S60W 32.60'

F-3)  
Found Rail Road Spike from the following:  
24" Elm S05E 42.59'  
30" Cherry S80W 92.25'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3) Section Corner 4, 5, 8 & 9, T7S, R4W  
Found 1/2" Iron Rod per A. Ringenberg's Records (LS#15103), and is accepted as a careful and faithful **reestablishment** of the position of the original corner. Replaced with a 1" Iron Rod with Hillsdale County Remonumentation Cap.  
PK Nail 30" Cherry N80E  
NW Cor. of NE Wing Wall of Bridge N65W 31.90'  
SW Cor. of SE Wing Wall of Bridge S60W 32.60'  
PK Nail Top R.R. Tie Fence Cor. N10W 30.75'

F-3) Section Corner 4 & 9, T7S, R4W  
Fnd R. R. Spike per L. 1, P. 512, Hillsdale Co., MI. and is accepted as a careful and faithful **reestablishment** of the position of the original corner. Replaced with a 1" IR with Hillsdale County Remonumentation Cap.  
95.78' PK Nail 18" Elm N60W 73.42'  
PK Nail 24" Elm S05E 42.59'  
PK Nail 12" Elm S45W 41.86'  
PK Nail 30" Cherry S80W 92.25'

Signed by \_\_\_\_\_ Date December 7, 1993

Surveyor's Michigan License No. 20712  
NO. 20712  
REGISTERED LAND SURVEYOR