

**SURVEY &
REMONUMENTATION**

LIBER 3 PAGE 4

DEC 15 1993

87703

RECORDED
HILLSDALE CO. MICH.

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

'93 DEC 8 AM 8 47

For corners in

Hillsdale
(County)

Located In:

Corner Code #/

1. Public Land Survey	T	<u>7S</u>	R	<u>4W</u>	<u>G-3</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Judy VanZandt
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3						●						
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R. Timothy Tietsema, in a field survey on November 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-3)

1823-GLO: Set original corner.

5/4/1972-David L. Boone LS#18803: Found Stone on approximate Centerline of Bankers Road and two (2) feet West of the N & S fenceline at a depth of three (3) feet. Stone has a flat side to the East and pointed on the North side.
Tele. Pole N'ly 52.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3)
Found 1/2" Iron Rod 0.3' below pavement and 1.5' South of the traveled Centerline of Bankers Road using the following:
Utility Pole N05E 51.92'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3) Section Corner 3, 4, 9 & 10, T7S, R4W
Found 1/2" Iron Rod per Liber 1, Page 103, Hillsdale County, Michigan, and is accepted as a careful and faithful reestablishment of the position of the original corner. Replaced with a 1" Iron Rod with, Hillsdale County Remonumentation Cap.
PK Nail Utility Pole N05E 51.92'
PK Nail Tw.12" Elm S60E 84.05'
PK Nail 8" Cedar N80E 104.85'
PK Nail 12" Pine S70W 72.76'

Signed by [Signature] Date December 7, 1993

Surveyor's Michigan License No. 20712

