

**SURVEY &
REMONUMENTATION**

1993

LIBER 3 PAGE 28

**COMMISSION REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED
88330 HILLSDALE CO. MICH.
'93 DEC 22 PM 2 22

Judy VanZandt
REG. OF DEEDS

For corners in

Hillsdale
(County)

Located in: Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>7S.</u> R <u>4W.</u> | <u>I-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

Frederick J. Cutcher

I, _____, in a field survey on December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	13	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

LCR Liber 1, Page 271, Mar. 7, 1973 by Robert E. Burris, Sr.: Set R.R. Spike from apparent lines of occupation. (See said LCR for sketch).

Stone and brick found by Geo. A. Mark, May 9, 1911, Book 9, Page 1405.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On this date I found R.R. Spike per references given by Robert E. Burris, Sr. LCR Liber 1, Page 271, Mar. 7, 1973.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced R.R. Spike with 3/4" x 36" steel rod with cap (County issue) in monument box.
- 3.7' West of centerline of M-49
- P.K. Nail in telephone pole N 67° E 61.18'
- P.K. Nail in Pwr. Pole S 47° W 96.04'
- Chisled sq. on top of Concrete X-over (culvert) S 77° W 60.87'
- S.W. cor. store bldg. fdn. S 50° E 147.60'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592

Date December 22, 1993