

1993

LIBER 3 PAGE 24

COMMISSION

88326

RECORDED
HILLSDALE CO. MICH.

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

'93 DEC 22 PM 2 2

For corners in

Hillsdale

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7S. R 4W. I-9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Judith VanZandt
REG. OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Frederick J.

Cutcher

in a field survey on December 22 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

LCR Liber 1, Page 35, Sept. 3, 1971 by A. John Hatt: Witness given by C.L. Herron in a survey May 16, 1931 as recorded in Book X, Page 297 in record of surveys at Register's Office.: "v" file mark under window of store bldg. West 36.75'; Iron cor. of bldg. S.E. 49.7'. Hatt set 1/2" iron rod from witnesses.

LCR Liber 1, Page 582, Aug. 21, 1978 by F. Cutcher: Found R.R. Spike matching above. (This corner is recorded in error as G-9 in LCR Liber 1, Page 582, Aug. 21, 1978).

This cor. also used by Olmstead in Survey dated July 7, 1972.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On this date I found a P.K. Nail fitting references as previously recorded.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced P.K. Nail with 3/4" x 36" steel rod with cap (County issue) in Monument box. In centerline intersection of roads. Top bolt Fire Hydrant N 42° E 47.68' N.W. cor. Bldg. S 40° E 50.03'; (Iron cor. of bldg. S.E. 49.7') S.E. cor. of bank N 22° W 101.26' East edge of sidewalk West 26.40'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by *Frederick J. Cutcher*

Date December 22, 1993

Surveyor's Michigan License No. 24592