

1993

88327

RECORDED HILLSDALE CO. MICH.

LIBER 3 PAGE 25

COMMISSION REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE '93 DEC 22 PM 2 22

Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt REG. OF DEEDS

For corners in Hillsdale (County)

Located In: Corner Code #

- 1. Public Land Survey T 7S. R 4W. I-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (10, G) contains a circled '1'.

Frederick J. Cutcher

I, Cutcher, in a field survey on December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Stone, earthen & glass found in a survey by Geo. A. Mark, recorded in Book 9, Page 33, County Surveyors Records for Hillsdale Co. MI.

LCR Liber 1, Page 165, Jul. 20, 1972 by Robert E. Burris, Sr.: Found R.R. Spike 6" below surface of road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On this date I found a R.R. Spike below surface of pavement as found and used by Burris. Two of Burris' references remain.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced R.R. Spike with 3/4" x 36" steel rod with cap (County issue) in monument box. 2.3'± South of board fence to East S.E. cor. brick garage N 84° W 89.35' S.E. cor. brick house #720 N 60° W 91.65' S.W. cor. house S 33° E 92.30' N.E. cor. house S 58° E 91.20'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Frederick J. Cutcher Surveyor's Michigan License No. 24592

Date December 22, 1993