

1993

LIBER 3 PAGE 26

COMMISSION REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

88328

RECORDED
HILLSDALE CO. MICH.

'93 DEC 22 PM 2 22

Judy VanZandt
REG. OF DEEDS

For corners in
Hillsdale

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7S. R 4W. I-11
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Frederick J. Cutcher

I, Cutcher, in a field survey on December 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

LCR Liber 1, Page 167, Jul. 20, 1972 by Robert E. Burris, Sr.: Burris states that there were no records available for this corner. Burris found R.R. Spike at surface of road. N 52° E 51.86' P.K. Nail in fence post; S 47° E 42.00' Drill hole in N.W. corner of stone pillar; West 36.94' P.K. Nail in fence post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On this date I could not find R.R. Spike. Used above references to reset corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" steel rod with cap (County issue) in monument box.
In centerline intersection of Edon Rd. & Lilac Rd.
N.W. cor. Stone Pillar S 46° E 42.00'
Top center of Telephone Stanchion N 49° E 50.76'
P.K. Nail in N. side fence post N 75° W 37.40'
Fence post N 52° E 51.86'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592

Date December 22, 1993