

1993

LIBER 3 PAGE 23

COMMISSION REMONUMENTATION 88325

RECORDED HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE

'93 DEC 22 PM 2 21

Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt REG. OF DEEDS

For corners in Hillsdale (County)

Located In: Corner Code #

Table with 3 columns: Description, Located In (S, T, R), and Corner Code #. Includes entries for Public Land Survey, Property Controlling, and Miscellaneous.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and a circled 'X' at row 9, column J.

Frederick J. Cutcher

I, Frederick J. Cutcher, in a field survey on December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Stone, earthen and glass. 16" Maple S 82° W 25.8'.

LCR Liber 1, Page 201, Oct. 2, 1972 by A. John Hatt: Found iron under pavement from N.E. corner of Lot #1 of the Plat of Highland Addition to the Village of Reading. Set R.R. Spike over iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On this date I found R.R. Spike over iron in centerline of East/West road.

This corner has been used on surveys in this area.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced R.R. Spike over iron with 3/4" x 36" steel rod with cap (County issue) in monument box. In centerline of East/West road.

- Telephone Pole N 30° E 42.00'
S.W. cor. house fdn. N 37° W 96.15'
S.E. cor. House fdn. N 10° W 67.70'
Center of Man Hole N 22° E 12.50'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Frederick J. Cutcher Date December 22, 1993
Surveyor's Michigan License No. 24592