

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 ON 10/30/97 AT A MEETING HELD ON 10/30/97 AL RINGENBERG, CD, REF

127744

RECORDED HILLSDALE CO. MICH.

'97 OCT 30 AM 10 18

HILLSDALE COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

SURVEY & REMONUMENTATION

FEB 11 1998

SECTION
Register of Deeds Stamp & File Number

For corners in

<u>Hillsdale</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>4W</u>	<u>L-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J. Cutcher, in a field survey on 9/22, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Original Government Survey by William Brookfield, 1825: Beech 7" S. 80° E. 14 links; Beech 12" N. 7° E. 20 links.

This corner was established by A.J. Hatt, RLS #9208, per LCRC dated 6-15-71 but never recorded (Records of Ringenberg). Hatt's LCRC stated no natural features available for witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
On 9-22-97 I found a P.K. nail over 1/2" square iron rod in centerline of Bankers Road and in line with tree row North and South.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I replaced above with Hillsdale County remonumentation bar with cap in monument box and is accepted as best available evidence of the position of the original corner.
In centerline of Bankers Road.
In line with row of Pines to North.
Top cen. tel. stan. N. 02° W. 29.08'
S.W. cor. house N. 22° E. 114.75'
S.E. cor. garage N. 63° E. 183.40'
Top cen. tel. stan. S. 12° W. 30.70'

Recorded by Frederick J. Cutcher
Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date October 9, 1997
10/9/97

