

SURVEY & REMONUMENTATION

DEC 15 1993

LIBER 3 PAGE 3

COMMISSION

87702

RECORDED
HILLSDALE CO. MICH.

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'93 DEC 8 AM 8 47

Judy Varnjandt
REG. OF DEEDS

For corners in

Hillsdale <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T 8S R 1W T 8S R 1W T R T R	G-13 H-13
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R. Timothy Tietsema, in a field survey on November 12, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13)
1823-GLO: Set original corner 65 links (42.90') East of Post between Sec. 03 & 04, T9S, R1W.
Ringenberg Records (date unknown) Fnd Stone w/"X" on top 14" Maple N40W 40.0'
NW Bldg Cor S40E 66.3'
NE Cor Sec 4 T9S, R1W WEST 42.8'
12/9/1970 Kurzy: Fnd large Stone, Replaced w/Iron
7/17/1980 A. Ringenberg LS#15103: Fnd Boat Spike
NW Bldg Cor S55E 65.94'

H-13)
1823-GLO: Set Original Corner.
7/17/1980 Allen Ringenberg LS#15103: Fnd Iron Pipe
Elec. Pole S55W 68.00'
Iron WEST 38.38'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13)
Found Boat Spike from the following:
1" Iron Pipe WEST 43.20' (NW Cor. Sec. 3, T9S, R1W)
24" Maple N07W 30.84'
NW Bldg Cor S40E 65.90'

H-13)
Found 1" Iron Pipe from the following:
Utility Pole S75W 68.95'
1/2" IR WEST 38.36'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13) Section Corner 33 & 34, T8S, R1W
Found Boat Spike per A. Ringenberg's Records (LS#15103), and is accepted as a careful and faithful **reestablishment** of the position of the original corner. Replaced with a 1" Iron Rod with Hillsdale County Remonumentation Cap.
PK Nail 24" Maple N60W 56.19'
PK Nail 22" Maple N20W 75.66'
NW Bldg Cor S40E 65.90'
NE Bldg Cor WEST 77.82'
1" IP (NW Cor. Sec. 3, T9S, R1W) WEST 43.20'

H-13) Section Corner 34, T9S, R1W
Fnd 1" Iron Pipe per A. Ringenberg's Records (LS#15103) and is accepted as a careful and faithful **reestablishment** of the position of the original corner. Replaced with a 1" Iron Rod with Hillsdale County Remonumentation Cap.
Nail Utility Pole S75W 68.95'
PK Nail Utility Pole S65E 192.82'
PK Nail Dbl 10" Birch N65W 225.22'
PK Nail 24" Maple N45W 181.99'
1/2" Iron Rod WEST 38.36'

Signed by _____ Date December 7, 1993

Surveyor's Michigan License No. 20712

