

SURVEY & REMONUMENTATION

LIBER 3 PAGE 2

DEC 15 1993

87701

RECORDED
HILLSDALE CO. MICH.

COMMISSION REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'93 DEC 8 AM 8 47

Judy VanZandt
REG. OF DEEDS

For corners in

<u>Hillsdale</u>	Located In:	Corner Code #/	
(County)			
1. Public Land Survey	T 8S R 1W	I-13	
	T 8S R 1W	K-13	
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, R. Timothy Tietsema, in a field survey on November 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-13)
1823-GLO: Set original corner 34 links (22.44') East of Post between Sec. 02 & 03, T9S, R1W.
9/29/1981-Allen Ringenberg LS#15103: Fnd 1/2" Iron Bar Power Pole S05W 33.93'
R.R. Spike (NE Cor Sec 3, T9S, R1W) WEST 22.46'
9/18/1986-Gerschbacher LS#18990: Fnd 1/2" Iron Bar 18" Catalpa S32W 70.78'
Power Pole N15W 105.05'

K-13)
1823-GLO: Set Original Corner 33 links (21.78') East of Post between Sections 1 and 2, T9S, R1W.
11/11/1986-Gerschbacher LS#18990 Set 5/8" Rebar w/cap Power Pole S05E 33.49'
6" S. Maple S45W 63.55'
28" W. Oak N80E 83.62'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13)
Found 1/2" Iron Rod from the following:
R.R. Spike WEST 22.45' (NE Cor. Sec. 3, T9S, R1W)
28" Catalpa S40W 69.81'
Utility Pole S05W 33.90'
Utility Pole N15W 105.10'

K-13)
Found 5/8" Iron Rod w/cap #18990 from the following:
Utility Pole SOUTH 33.50'
10" Hickory S50W 63.43'
32" Maple N85E 83.58'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13) Section Corner 34 & 35, T8S, R1W
Found 1/2" Iron Rod per Liber 552, Page 27, Hillsdale Co., MI, and is accepted as a careful and faithful **reestablishment** of the position of the original corner. Replaced with a 1" Iron Rod with Hillsdale County Remonumentation Cap.
PK Nail 28" Catalpa S40W 69.81'
PK Nail Utility Pole S05W 33.90'
PK Nail 18" Elm S55W 60.63'
PK Nail Utility Pole N15W 105.10'
R. R. Spike (NE Cor. Sec. 3, T9S, R1W) WEST 22.45'

K-13) Section Corner 35 & 36, T8S, R1W
Fnd 5/8" IR w/cap per L. 555, P. 441, Hillsdale Co., MI., and is accepted as a careful and faithful **reestablishment** of the position of the original corner. Replaced with 1" Iron Rod with Hillsdale County Remonumentation Cap.
PK Nail Utility Pole SOUTH 33.50'
PK Nail Utility Pole N10E 32.05'
PK Nail 10" Hickory S50W 63.43'
PK Nail 32" Maple N85E 83.58'
PK Nail 15" Cherry S40E 61.06'

Signed by _____ Date December 7, 1993

Surveyor's Michigan License No. 20712

