

**SURVEY &  
REMONUMENTATION**

LIBER 3 PAGE 1

DEC 15 1993

87700

RECORDED  
HILLSDALE CO. MICH.  
'93 DEC 8 AM 8 47

**REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
COMMISSION**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Hillsdale</u> <small>(County)</small>	Located In:	Corner Code #/1
1. Public Land Survey	T 8S R 1W	M-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Judy VanZandt*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, R. Timothy Tietsema, in a field survey on November 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-13)  
1823-GLO: Set original corner.  
1948-MDOT Road Plans: Fnd. 1/2" Square Bar 1/2' below surface, 7.68' Right (East) of Centerline, Station 74+98.55.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13)  
Found 1/2" Iron Rod in Monument Box 1.0' below surface, 6.8' East of the traveled Centerline of U.S. 127.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13) Section Corner 36, T8S, R1W  
Found 1/2" IR in Mon. Box per MDOT Road Plans (1948) for U.S. 127, and is accepted as a careful and faithful **reestablishment** of the position of the original corner. Replaced with a 1" Iron Rod with Hillsdale County Remonumentation Cap.  
PK Nail Guy Pole N50E 57.36'  
MDSH Nail & Washer Utility Pole N55W 73.29'  
PK Nail 12" Cedar N30W 94.60'  
Conc. R/W Marker N70W 70.01'  
PK Nail 12" Apple N70E 40.02'

Signed by *R. Timothy Tietsema* Date December 7, 1993

Surveyor's Michigan License No. 20712 NO. 20712

