



REMONUMENTATION

LIBER 3 PAGE 335

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

025217

For corners in

HILLSDALE

(County)

Located in:

Corner Code #

1. Public Land Survey

T8S R 2W

B-9

T	R	
T	R	
T	R	
T	R	
S	T	R
S	T	R
S	T	R
S	T	R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
HILLSDALE CO. MICH.
29 NOV 29 AM 9:16

Jeffrey A. Bieszk
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, Jeffrey A. Bieszk, in a field survey on 25 Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Wm. Brookfield. (1825)
11" Poplar N52E 75 lks.
9" Elm S47E 75 lks.

Survey Donald Olmstead L1-P720
Set iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Did not find iron as set by Olmstead. Measured from A-9 to C-9 this distance was the same as Olmsteads survey, set corner from said survey which Olmstead set corner from survey done by R.J. Caryell 1889 survey # 1082. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Set witness iron East 20.00 ft.
Set witness iron West 20.00 ft.
Nail w/tag 40" Oak N 05 W 27.04 ft.
Nail w/tag 8" Oak S 05 E 42.70 ft.



Signed by *Jeffrey A. Bieszk*
Surveyor's Michigan License No. 41093

Date 24 November 1999