



REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3 PAGE 337

025219

For corners in

<u>HILLSDALE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8</u> S R <u>2</u> W	<u>D-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECORDED
HILLSDALE CO. MICH.

NOV 29 AM 9:16

Jeffrey A. Bieszk
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Bieszk, in a field survey on 25 Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9				●									
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Wm. Brookfield. (1825)	Survey Geo. Mark Co. Surveyor
6" Ironwood S58E 50 lks	Stone and Stake
13" Beech S65W 30 lks.	8" Beech N35.75W 73 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Did not find any iron. Took proportionate measurement from C-9 to E-9, point landed 1 foot South centerline of Camden Road on occupation to the South. Dug and found nothing. Set corner at proportionate distance and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box		
Nail w/tag fence post	S 05 W	26.00 ft.
Steel fence post	N 05 W	33.38 ft.
Nail w/tag 3" Cedar	N 20 W	33.12 ft.
Nail w/tag 30" Oak	South	24.62 ft.



Signed by *Jeffrey A. Bieszk*
Surveyor's Michigan License No. 41093

Date 24 NOVEMBER 1999