



REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3 PAGE 342

025224

RECORDED
HILLSDALE CO. MICH.

NOV 29 AM 9:17

Jeffrey A. Bieszk
REGISTERED

Register of Deeds Stamp & File Number

For corners in

HILLSDALE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 8S R 2W I-9

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Jeffrey A. Bieszk, in a field survey on 25 Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9									●				
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Wm. Brookfield. (1825)
18" Beech N74.5E 10 lks
12" Beech S32E 28 lks.

LCRC Alan Ringenberg L2-P11
Found R.R. spike
PK in P. Pole N60W 188.65 ft.
Phone riser N60E 62.36 ft.
NW Cor. Barn S10E 189.05 ft.
Phone riser S60W 57.88 ft.

LCRC Donald Olmstead L2-P57
Found Spike
Stop sign NW 50.80 ft.
Road Sign NE 55.6 ft.
Iron Rod SE 46.6 ft.
Iron Rod SW 48.3 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. Spike same as Ringenberg and Olmstead's LCRC. Corner is in the centerline of Camden Road and Tripp Road. Dug and found no other evidence and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box		
Nail w/tag 6" Locust	N 65 E	65.41 ft.
Road Sign	N 40 W	53.41 ft.
Phone riser	S 50 W	57.98 ft.
Stop Sign	S 15 E	45.86 ft.



Signed by *Jeffrey A. Bieszk*
Surveyor's Michigan License No. 41093

Date 24 November 1999