



REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3 PAGE 344

For corners in

HILLSDALE  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>8</u> S	R <u>2</u> W	<u>K-9</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

025226  
RECORDED  
HILLSDALE CO. MICH.  
2010/29 AM 9:17  
*Jeffrey A. Bieszka*  
PUBLIC DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Jeffrey A. Bieszka, in a field survey on 25 Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Wm. Brookfield. (1825)	LCRC Donald Olmstead L2-P56
11" Beech S34W 28 lks.	Found R.R. Spike
18' Beech S14W 21 lks.	Telephone Box NW 44.4 ft.
	Iron Fence post NE 41.2 ft.
	Stop Sign SE 46.98 ft.
	Telephone Pole SW 54.3 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike centerline of Camden Road and Gilbert Road. Dug and found no other evidence and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box		
Fence Post	N 50 E	41.40 ft.
Stop Sign	N 20 W	45.00 ft.
Nail w/tag Utility Pole	S 20 W	54.61 ft.
Stop Sign	S 15 E	49.34 ft.



Signed by [Signature]  
Surveyor's Michigan License No. 41093

Date 24 November 1999