



HILLSDALE COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

For corners in

HILLSDALE COUNTY
WOODBIDGE TWP (County)

Located in:

Corner Code #

- 1. Public Land Survey T. 8 S. R. 3 W. I-7
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCTOBER 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

CORNER COMMON TO SECTIONS 14-15-22-23

A. Description of original monument and accessories and/or subsequent restoration:

1825: GOVERNMENT SURVEY, CORNER SET
1873: R. BULLARD, SURVEYOR - BLUE GRANITE STONE, BRICK, GLASS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE 4" BELOW NEW PAVED SURFACE, 8" BELOW FOUND PIECES OF BRICK, BUT NO STONE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

- SW CORNER TEL PED N 38 E 49.35'
- SE CORNER TEL PED N 54 W 60.69'
- NW CORNER HOUSE S 50 E 75.80'
- TAG IN E. SIDE POWER POLE S 15 W 184.50'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W Reed*



Date NOVEMBER 9, 1998

Surveyor's Michigan License No. 33985

EDWARD R. REED