

'98 NOV 25 AM 9 59



HILLSDALE COUNTY REMONUMENTATION CORNER
LAND-CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

For corners in

HILLSDALE COUNTY
WOODBRIDGE TWP (County)

Located In: Corner Code #

- 1. Public Land Survey T 8 S R 3 W J-5
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

SURVEY &
REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5										●			
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EDWARD W. REED, in a field survey on OCTOBER 24, 1998
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 11 & 14

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: GOVERNMENT SURVEY - CORNER SET
- 1873: R. BULLARD, SURVEYOR - STONE
- 1974: D. OLMSTEAD, SURVEYOR - SET PK NAIL IN CENTER LINE OF ROAD AND PROPRATED DISTANCE, RECORDED LCRC #5386

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

UNABLE TO LOCATE P.K. NAIL SET BY OLMSTEAD OR RESET FROM OLD WITNESS - FOUND NAIL SET BY UNKNOWN SURVEYOR ON LINE BETWEEN CORNERS EAST AND WEST AND ON LINE WITH OLD FENCE LINE RUNNING NORTH. POINT IS NOT MIDWAY.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 30" REBAR IRON AND REMON CAP, ON LINE BETWEEN CORNERS EAST AND WEST IN LINE WITH FENCELINE RUNNING NORTH AS USED BY PREVIOUS SURVEYORS: SET CI - MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE.

WITNESS:
 2" ROUND STEEL POST NORTH. 28.00
 IN LINE WITH FENCELINE RUNNING NORTH
 WITNESS TAG NORTH WEST SIDE 24" MAPLE S 50 W 51.58
 WITNESS TAG SOUTH SIDE 24" HICKORY N 70 E 87.70

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

Date NOVEMBER 9, 1998

Surveyor's Michigan License No. 33985 EDWARD R. REED

