ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON
AL RINGENBERG, CO REP

12015

LIBER 3 PAGE 274

RECORDED
HILLSDALE CO. MICH.
'98 NOV 25 AM 9 59
REG. OF DEEDS

HILLSDALE COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION
FEB 23 1999
SECTION

Register of Deeds Stamp & File Number

For corners in

HILLSDALE COUNTY
WOODBRIDGE TWP (County)

		Located In:	Corner Code #
1. Public Land Survey		T 8 S R 3 W	J-7
		T___ R___	
		T___ R___	
		T___ R___	
2. Property Controlling	S___	T___ R___	
in Section	S___	T___ R___	
3. Miscellaneous	S___	T___ R___	
Property in Sec.	S___	T___ R___	

4. Lot No. _____ , Recorded Plat _____

5. Private Claims _____



I, EDWARD W. REED, in a field survey on OCTOBER 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 14 & 23

A. Description of original monument and accessories and/or subsequent restoration:

1825: GOVERNMENT SURVEY, CORNER SET
1873: R. BULLARD, CO SURVEYOR - ROCK FOR CORNER
1966: A.J. HATT, SURVEYOR - NOTES INDICATE FOUND STONE, PLACE IRON PIPES HORIZONTALLY ON TOP
1974: D. OLMSTEAD, SURVEYOR - UNABLE TO LOCATE STONE, RESET CORNER FROM PRO RATED RECORD DISTANCE AND OLD ESTABLISHED FENCE LINES, RECORDED IN LCRC 5179

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND OLD STONE (3' X 3') WITH IRON PIPES OVER TOP, ALSO ½" X 18" BOLT ALONG SIDE WITH FLAGGING AS DESCRIBED BY HATT.
ALSO FOUND IRON AS DESCRIBED BY OLMSTEAD AS WITNESS IN LCRC 5179 3.85 FEET EAST OF STONE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" IRON ROD WITH REMON CAP IN CI-MONUMENT OVER STONE AS FOUND BY HATT, SET MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE

18" WALNUT	N 05 E	33.45 TO PK NAIL WEST SIDE
POWER POLE	SOUTH	78.54 TO TAG ON W SIDE
POWER POLE	N 33 E	90.72 TO TAG ON W SIDE
STEEL ANGLE IRON POST	SOUTH	23.25' TO NEAR FACE
NW CORNER HOUSE	S 56 E	103.33'
OLMSTEAD IRON (LCRC)	EAST	3.85'
	SOUTH	0.80'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

STATE OF MICHIGAN
EDWARD W. REED
LAND SURVEYOR
NO. 33985
LICENSED LAND SURVEYOR

Signed by Edward W. Reed

Date NOVEMBER 9, 1998

Surveyor's Michigan License No. 33985 EDWARD R. REED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 197
REVISED MAY 14,1975
REVISED JAN., 198
REVISED OCT., 199