

12011

RECORDED  
HILLSDALE CO. MICH.

'98 NOV 25 AM 9 58

*Judy Wanzandt*  
REC. # DEEDS



LIBER 3 PAGE 270

HILLSDALE COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE COUNTY  
WOODBIDGE TWP (County)

Located In: Corner Code #

1. Public Land Survey	T <u>8</u> S	R <u>3</u> W	<u>K-5</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

SURVEY &  
REMONUMENTATION

Register of Deeds Stamp & File Number

FEB 23 1999

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_ SECTION \_\_\_\_\_

I, EDWARD W. REED, in a field survey on OCTOBER 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 11-12-13-14

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: GOVERNMENT SURVEY - CORNER SET
- 1900: G. MARK, SURVEYOR - STONE
- 1966: A.J. HATT, SURVEYOR - FOUND IRON 2" BELOW PAVEMENT SET RAILROAD SPIKE FLUSH WITH PAVEMENT
- 1971: A.J. HATT, SURVEYOR - RECORDED CORNER IN LCRC # 3428

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE IN SURFACE OF PAVEMENT, FOUND RAILROAD SPIKE 4" BELOW 1st RAILROAD SPIKE, FOUND 1/2" X 24" IRON ROD ALONG SIDE SPIKES, ALL FITTING WITNESSES OF LCRC # 3428, NO STONE FOUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

FACE OF CONCRETE POST	NORTH	27.95'
TOP CENTER TEL PED	N 55 W	59.8'
TOP CENTER TEL PED	S 59 W	61.3'
TOP END CMP	S 15 E	54.8'
TAG IN W SIDE POWER POLE	N 45 E	43.17'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*  
Surveyor's Michigan License No. 33985 EDWARD R. REED

Date NOVEMBER 9, 1998

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

