



98 NOV 25 AM 9 58

Judy Vanjandt  
REG. OF DEEDS

HILLSDALE COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE COUNTY  
WOODBIDGE TWP (County)

Located In: Corner Code #

- 1. Public Land Survey T 8 S R 3 W M-5
- 2. Property Controlling in Section S      T      R
- 3. Miscellaneous Property in Sec. S      T      R

SURVEY &  
REMONUMENTATION

FEB 23 1999

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on OCTOBER 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHEAST CORNER SECTION 12,  
NORTHEAST CORNER SECTION 13

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: GOVERNMENT SURVEY - CORNER SET
- 1894: GEO. MARK, SURVEYOR - STONE (+) CROSSED
- 1988: A. RINGENBERG, SURVEYOR - IRON & WITNESS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE FITTING WITNESS OF RINGENBERG, ALSO FITTING OFFSET OF 10 LINKS FOR RANSON TOWNSHIP, UNABLE TO FIND ANY OTHER EVIDENCE OF CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

RANSON CORNER	SOUTH	6.6'
SW CORNER CONC. HEADWALL	N 30 E	29.38'
SE CORNER CONC. HEADWALL	N 45 W	37.25'
NE CORNER TEL PED	S 70 W	56.43'
SW CORNER TEL PED	N 82 E	101.58'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

Date NOVEMBER 9, 1998

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

