



127732

RECORDED HILLSDALE CO. MICH.

LIBER 3 PAGE 191 HILLSDALE COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'97 OCT 30 AM 10 18

Justy VanZandt PEACE SEEDS

For corners in

Hillsdale (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>6</u> T <u>8S R4W</u>	<u>A-2</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frederick J. Cutcher, in a field survey on 4/29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not set on original G.L.O. survey.

George Mark, 6/5/1886: Stone; Sug. 18" N. 22 1/2° E. 122 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Measured lines of occupation South from corner A-1 for one mile and dug for corner A-2. Found pinch top iron 1.8' below road surface 0.5' East of centerline Kelly Road and opposite concrete post to East.

SURVEY & REMONUMENTATION

FEB 11 1998

SECTION

Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set County remonumentation bar with cap in monument box over pinch top iron. This position was not established on G.L.O. survey. This monument is accepted as the best available evidence of the position of the corner.

- Top S.W. cor. conc. post East 26.38'
- Top cen. tel. stan. S. 20° W. 94.47'
- Top cen. tel. stan. S: 28° W. 60.58'
- S. end C.M.P. N. 5° W. 205.25'
- 227'± S. of centerline Pridgeon Road

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date 10/29/97

