



127733

LIBER 3 PAGE 192
HILLSDALE COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
HILLSDALE CO. MICH.
'97 OCT 30 AM 10 18

Judy Wanzandt
REC. OF DEEDS

For corners in

<u>Hillsdale</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>6</u> T <u>8S</u> R <u>4W</u>	<u>B-1</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J. Cutcher, in a field survey on 4/29, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1	●											
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
This corner was not set on original G.L.O. survey.

George Mark, 6/5/1886: Stone.

LCRC Liber 1, Page 473, Apr. 16, 1975 Olmstead: 3/4" I.P. 118.92' West of B-13, T7S, R4W; (see sketch of Olmstead's references on above LCRC).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 3/4" iron pipe and one of Olmstead's references.

SURVEY &
REMONUMENTATION

FEB 11 1998

SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set County remonumentation bar with cap over 3/4" iron pipe found. This position was not established on G.L.O. survey. This monument is accepted as the best available evidence of the position of the corner.

- 14' North of centerline Brush Road.
- 3" steel corner post S. 15° W. 34.00'
- Top cen. tel. stan. S. 60° E. 85.35'
- Top cen. tel. stan. N. 72° E. 93.20'
- P.K. & spotter E. side power pole N. 35° W. 137.10'

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date October 29, 1997