


'98 DEC 1 AM 9 15

LIBER 3 PAGE 284



HILLSDALE COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Julie VanZandt
REG. OF DEEDS

For corners in

SURVEY &
REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

HILLSDALE COUNTY
CAMDEN TWP (County)

Located In: Corner Code #

1. Public Land Survey	T <u>8</u> S <u>R</u> 4 W	<u>C-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on NOVEMBER 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHWEST CORNER SECTION 20
NORTHWEST CORNER SECTION 29

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: GOVERNMENT SURVEY - CORNER SET
- 1921: C.L. HERRON, SURVEYOR - TIED PLAT OF "HARTS PLAT OF OAK GROVE BEACH" TO CORNER
- 1926: C.L. HERRON, SURVEYOR - TIED PLAT OF "HARTS PLAT OF OAK GROVE BEACH NO 1" TO CORNER


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE WITH BRICK ON 2 SIDES IN FENCE LINE RUNNING NORTH-SOUTH & EAST

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 3/4" IRON ROD IN CI-MONUMENT BOX

WOOD ANCHOR POST	SOUTH	2.00' TO FACE
12" PINE	S 58 W	9.4' TO CENTER
12" TWIN LOCUST	SOUTH	5.4' TO CENTER
RR TIE POST	S 75 E	20.6' TO FACE
C/L ROAD	NORTH	89.0' TO CENTER
RR TIE POST@ END OF FENCE	NORTH	65.5' TO FACE

PLACED CARSONITE MARKER ALONG SIDE POINT
IN FENCE LINE RUNNING NORTH-SOUTH AND EAST



AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
Surveyor's Michigan License No. 33985 EDWARD R. REED

Date 11-25-98