

007947
RECORDED
HILLSDALE CO. MICH.

'98 AUG 7 AM 10 10

Judy VanZandt
REG. OF DEEDS

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1997 AT A MEETING HELD ON _____ AT RINGENBERG, CO. REP.

HILLSDALE COUNTY REMONUMATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE COUNTY
Camden Township

Located In: Corner Code

1. Public Land Survey T 8 S R 4 W E-7
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____
T _____ R _____
3. Miscellaneous S _____
T _____ R _____
Property in Sec. S _____
T _____ R _____

SURVEY &
REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 26, 19 98
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Quarter corner common to sections 16 & 21

A. Description of original monument and accessories and/or subsequent restoration:

1825: ROBERT CLARK JR, DEPT SURVEYOR - CORNER SET
1869: GEO. MARK, CO SURVEYOR - SURVEY NO 522, STONE 28 INCHES & EARTHEN
1980: FRED CUTCHER, SURVEYOR - FOUND LARGE STONE WITH 1" SOLID IRON ON NORTH SIDE, SET HARRISON MARKER, RECORDED IN LCRC LIBER 2, PAGE 32

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE & HARRISON MARKER DESCRIBED BY CUTCHER IN LIBER 2, PAGE 32

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED HARRISON MARKER WITH 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE

CORNER IS ON NORTH EDGE OF E-W ROAD & ABOUT IN LINE WITH CENTERLINE OF ROAD TO SOUTH

12' WEST OF FENCE TO NORTH
FACE OF STEEL GATE POST, N 85 E 19.25'
POWER POLE, S 50 W 133.35'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*

Date AUGUST 5, 1998

EDWARD W. REED

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

