

007945

RECORDED  
HILLSDALE CO. MICH.  
98 AUG 7 AM 10 10

LIBER 3 PAGE 258

HILLSDALE COUNTY REMONUMATION CORNER,  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1968 AT A MEETING HELD ON AL RINGENBERG, CO. RBP

*Judy VanZandt*  
REG. OF DEEDS

For corners in

HILLSDALE COUNTY  
CAMDEN TWP.

Located In: Corner Code

1. Public Land Survey T 8 S R 4 W G-8  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_  
T \_\_\_ R \_\_\_ SURVEY &  
REMONUMENTATION  
3. Miscellaneous S \_\_\_  
T \_\_\_ R \_\_\_ FEB 23 1999  
Property in Sec. S \_\_\_  
T \_\_\_ R \_\_\_ SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on AUGUST 3, 19 98  
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21	●	22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 21 & 22

A. Description of original monument and accessories and/or subsequent restoration:  
5-16-74: M. VERNIER; SURVEY CHIEF OF RINGENBERG & BURRIS, SURVEYORS  
INDICATE IRON PIPE WITH ID CAP SET:  
5-30-74: ROBERT BURRIS, SURVEYOR: SURVEY TIED TO CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

IRON PIPE NOW GONE DUE TO ROAD RECONSTRUCTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
RESET CORNER FROM EXISTING WITNESS OF FIELD NOTES OF RINGERBERG & BURRIS  
SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 6" BELOW GRAVEL ROAD SURFACE

NAIL & WASHER IN W. SIDE 12" TRIPLE OAK NORTH 44.37'  
PK NAIL IN E. SIDE OF TWIN 10" OAK N 20 E 49.6'  
PK NAIL IN NE SIDE 24" SHAG HICKORY S 55 E 179.7'  
16" STUMP N 50 W 55.94'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*  
EDWARD W. REED

Date AUGUST 23 1998

Surveyor's Michigan License No. 33985

