

ACCEPTED BY THE HILLSDALE COUNTY
SURVEY PFR GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
12/1/98
AL RINGENBERG, CO. REP.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>HILLSDALE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>4W</u>	<u>H-9</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Julie VanZandt
REG. OF DEEDS
**SURVEY &
REMONUMENTATION**
FEB 23 1999
SECTION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Bieszk, in a field survey on 25 Nov, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9								●					
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO
post
13" Beech N85E 35 lks
7" Beech N66.5W 30 lks

County Surveyor (Geo. A. Mark 1871)
Stone, Brick & Earthen

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK in centerline of Camden Road and M-49, dug under and found a railroad spike below, did not find anything else. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Nail & Tag Power Pole N 40 W 32.48 ft.
Nail & Tag Power Pole N 60 E 57.09 ft.
Nail & Tag Power Pole S 45 E 35.47 ft.
Nail & Tag Power Pole S 40 W 37.68 ft.



Signed by *Jeffrey A. Bieszk*
Surveyor's Michigan License No. 41093

Date 4 December 1998