



LIBER 3 PAGE 303

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE (County)	Located In:	Corner Code #
1. Public Land Survey	T 8S R 4W	I-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Jeffrey VanZand
REC. OF DEEDS

**SURVEY &
REMONUMENTATION**

FEB 23 1999

SECTION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Bieszk, in a field survey on 25 Nov, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO
Post
5" Oak N42W 42 lks
7" Elm N73E 15.5 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found remains of a fence running West dug along fence to I found remains of fence running North and South, dug around until I found original fence corner. Than I found pieces of small rocks with no evidence of rocks really being in the area around. Accepted post as the best available evidence to position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Nail & Tag 12" Ash N 10 E 28.26 ft.
Nail & Tag 8" Ash N 80 E 15.68 ft.
Nail & Tag 24" Twin Ash South 24.10 ft.
Nail & Tag 12" Twin Ash N 70 W 8.53 ft.



Signed by *[Signature]*
Surveyor's Michigan License No. 41093

Date 4 Dec 1998