

12406

RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 304

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE '98 DEC 4 AM 11 48
Filing Requirement of Act 74, Mich. P.A. 1970

ACCEPTED BY THE HILLSDALE LOCAL SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT 78A MEETING HELD ON 10-6-98
AL RINGENBERG, CO. REP.

For corners in

HILLSDALE (County)	Located In:	Corner Code #
1. Public Land Survey	T 8S R 4W	I-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Justy VanZandt
REG. OF DEEDS
SURVEY & REMONUMENTATION
FEB 23 1999
SECTION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Bieszk, in a field survey on 25 Nov, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO post 18" Elm N62E 15 lks 13" Elm N61W 67 lks	County Surveyor (Geo. A. Mark 1876) Stone & Stake 14" W. Oak N15W 154.5 lks Stone South 50 lks
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron unreadable, iron was on line with fence to the South, dug under and did not find stone. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Nail & Tag Triple Boxelder S 40 W 41.72 ft.
Nail & Tag Twin Maple S 05 E 37.31 ft.
Nail & Tag 12" Maple N 40 W 34.83 ft.
Village Limit Sign S. leg N 82 W 99.37 ft.



Signed by *Jeffrey A. Bieszk*
Surveyor's Michigan License No. 41093

Date 4 December 1998