

118876

LIBER 3 PAGE 173

RECORDED  
HILLSDALE CO. MICH.

'97 JAN 13 AM 11 57



REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt  
REG. OF DEEDS

For corners in <u>HILLSDALE</u> (county)	Located In		Corner Code #
1. Public Land Survey	T <u>9S</u>	R <u>2W</u>	<u>M-3</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S <u>T</u>	R _____	_____
	S <u>T</u>	R _____	_____
3. Miscellaneous Property in Sec.	S <u>T</u>	R _____	_____
	S <u>T</u>	R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, R.T. Tietsema, in a field survey on JUNE 20, 1996, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management of by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or restoration:

Set post Corner of Sections 1, 2, 7 & 12

Date	Name	Section	Method	Description	Measurements
2/08/1823	GLO (Brookfield)		Fld. Notes	Set Original Corner	1) 11" Beech S86W 31 links(20.46') 2) 6" Ironwood N29W 35 links(23.1')
no date	no name		County Road drawings	Large Stone in CL of N-S road, S road W.	3) Cor. Fence Post NW 43.00' 4) Cor. Fence Post NE 38.00' 5) Cor. Fence Post NE 89.70'
August 1957	D.C.P.	3165	Resurvey	Set 5/8" Iron Rod over Large Stone with cross.	6) SW Cor., Sec. 6, T9S, R1W NO 59.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September of 1996 LSC found a 5/8" Boat Spike 0.60' below the asphalt surface in range of occupation to the West, North & South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon Box over existing Boat Spike, established four (4) witnesses.

- 7) Power Pole N13W 176.72' to P.K. in East side of pole.
  - 8) NW Cor. Conc. Hdwl N85E 45.47'
  - 9) SW Cor. Conc. Hdwl S50E 61.64'
  - 10) CL of Rd. Int. S05W 19.88'
- Territorial & Pittsford

is our opinion that this represents the best evidence of the position of the original corner.

signed by [Signature] Date DEC 20 1996  
Surveyor's Michigan License No. 20712

SURVEY & REMONUMENTATION

MAY 16 1997