



118386

RECORDED HILLSDALE CO. MICH.

LIBER 3 PAGE 119 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'96 DEC 19 PM 2 19

Handwritten signature: Jeffrey VanZandt REG. OF DEEDS

For corners in

Table with columns: HILLSDALE (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. A dot is marked at row 3, column C.

JEFFREY BIESZK in a field survey on 10 DECEMBER 19 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO POST 15 ELM S22W 8 lks 16 W. ASH S62.5E 30 lks

MARK STAKE UNDER BRIDGE 6 APPLE N66.75E 116.75 lks

KELLER SURVEY LIBER 547 PAGE 939 SET PK AT INTERSECTION OF CARPENTER RD AND TERRITORIAL ROAD AT 148 FEET WEST OF CORNER IN BRIDGE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GEORGE MARK FOUND STAKE IN RIVER AND UNDER BRIDGE. I DID NOT FIND THIS STAKE BUT THERE HAS BEEN LOT OF ROAD WORK IN THIS AREA. FOUND PK SET BY KELLER AT INTERSECTION OF ROADS AND TIED INTO HIS SURVEY AND REESTABLISHED THE CORNER. THIS LANDED ON THE BRIDGE, AND SET A PK. ALSO SET TWO WITNESS CORNERS ON EITHER SIDE OF THE BRIDGE.. THE PK IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY & REMONUMENTATION

MAY 1 6 1997


COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3: SET PK ON BRIDGE NW COR BRIDGE RAIL N75W 26.09' NE COR BRIDGE RAIL N65E 22.63' SE COR BRIDGE RAIL SOUTH 15.81' SW COR BRIDGE RAIL S55W 46.26'

WITNESS CORNER WEST 40' WEST C-3 ON SECTION LINE NW COR BRIDGE RAIL N40E 18.21' SW COR BRIDGE RAIL S05W 16.00' R/W MARKER N35W 83.17' 24" OAK S40W 76.80' SET 5/8" x 36" REBAR IN MON BOX

WITNESS CORNER EAST 30' EAST C-3 ON SECTION LINE NE COR BRIDGE RAIL N20W 13.03' SE COR BRIDGE RAIL S35W 32.70' SOUTH RAIL EAST POST N50E 43.21' NORTH RAIL EAST POST N45E 46.00' SET 5/8" x 36" REBAR IN MON BOX



Signed by [Handwritten Signature]

Date 12 DECEMBER 1996

Surveyor's Michigan License No. PS# 41093