

ACCEPTED BY THE HILLSDALE COUNTY SURVEY FEES GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1896 AT A MEETING HELD ON \_\_\_\_\_ AL RINGENBERG, CO. REC.

LIBER 3 PAGE 121  
REMONUMENTATION

118388

RECORDED  
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE

'96 DEC 19 PM 2 19

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE (County)	Located In:	Corner Code #
1. Public Land Survey	T 9S R 3W	F-3 G-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Justy VanZandt*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, JEFFREY BIESZK, in a field survey on 10 DECEMBER, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-3:  
1837 GLO  
POST  
9 BEECH S51E 15 lks  
8 BEECH S20.5W 15 lks

JOHN HATT  
LCRC L1 P45  
SET R.R. SPIKE  
5.4 FEET NORTH OF CENTERLINE  
15" HICKORY N75E 90.23'

G-3:  
1837 GLO  
POST  
12 W. OAK N17E 16 lks  
10 W. OAK N53.5W 21 lks

DONALD OLMSTEAD  
LCRC L2 P49  
SET 3/4" PIPE  
3/4" PIPE NORTH 33'  
3/4" PIPE SW 33.15'

GEORGE MARK  
STONE AND BRICK  
NO WITNESS

GEORGE MARK  
23 STONE & BRICK N45W 70 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3: JOHN HATT SET R.R. SPIKE ON LINE BETWEEN E-3 AND G-3 AT 2642.14 FEET FROM E-3 AS MARKS DID IN BOOK 1, PAGE 119. I FOUND R.R. SPIKE AS SET BY HATT WHICH FIT OCCUPATION FENCE LINE TO THE NORTH AND ALSO FITS THE PLATS TO LAKE DIANE. ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

G-3: DONALD OLMSTEAD FOUND PK IN CENTERLINE OF ROAD WHICH AS 2640 FROM G-2. WHICH HE BELIEVED THAT JOHN HATT SET WHEN LAKE DIANE WAS SURVEYED. IRON FITS THE PLATS TO LAKE DIANE AND SURVEY DONE BY OLMSTEAD. ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3:  
SET 5/8" x 36" REBAR W/CAP IN MON BOX  
17" W. OAK N55E 88.65'  
10" W. OAK N75W 52.93'  
15" ASH S15W 37.72'  
10" HICKORY S50E 76.42'

G-3:  
SET 5/8" x 36" REBAR W/CAP IN MON BOX  
STOP SIGN POST S10E 47.50'  
NAIL & TAG S. POST SIGN NORTH 35.08'  
NAIL & TAG POWER POLE N30W 57.66'  
CENTER RISER N20E 41.53'



SURVEY &  
REMONUMENTATION

MAY 16 1997

COMMISSION

Signed by [Signature]  
Surveyor's Michigan License No. PSA 41093

Date 10 DECEMBER 1996