



LIBER 3 PAGE 122  
REMONUMENTATION

118389

RECORDED  
HILLSDALE CO. MICH.

'96 DEC 19 PM 2 19

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Jeffrey Bieszk*  
REG. OF DEEDS

For corners in

HILLSDALE (County)	Located In:	Corner Code #:
1. Public Land Survey	T 9S R 3W	H-3 I-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, JEFFREY BIESZK, in a field survey on 10 DECEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-3:  
1837 GLO  
40 WHITE WOOD S85W 43 lks  
18 R. OAK S27E 26 lks  
  
DONALD OLMSTEAD  
LCRC L2 P49  
SET R.R. SPIKE  
3/4" IP NW 48.95'  
FNC POST SW 71.20'

ALAN RINGENBERG  
LCRC L2 P63  
FOUND R.R. SPIKE  
1" BAR NORTH 48.54'  
WEST END 12" CUL. S35E 26.05'  
FNC POST S60W 66.35'  
SE TURNER HEADSTONE S10E 46.44'

I-3:  
1837 GLO  
15 BEECH S08E 31 lks  
18" BEECH S79W 16 lks  
  
DONALD OLMSTEAD  
SURVEY L1 P391  
SET R.R. SPIKE  
YIELD SIGN NW 58.5'  
STOP SIGN POST SW 65.1'  
FNC POST SE 40'  
LAKE DIANE SIGN NE 57.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3: DONALD OLMSTEAD SET CORNER BY SINGLE PROPORTIONAL MEASUREMENT FROM G-3 AND I-3. CORNER FITS FENCE TO THE NORTH AND IS 5.5 FEET SOUTH OF CENTERLINE OF ROAD EAST AND WEST. DID NOT FIND ANYTHING ELSE. ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

I-3: DONALD OLMSTEAD SET CORNER FROM KNOWN CORNERS. I FOUND R.R. SPIKE AS WITNESSED AND HAD SAME MEASUREMENT TO H-3 AS DID OLMSTEAD. DID NOT FIND ANYTHING ELSE. ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3:  
SET 5/8" x 36" REBAR IN MON BOX  
NAIL & TAG 16" WALNUT NORTH 46.28'  
CENTER RISER N55W 79.46'  
NAIL & TAG 30" WALNUT S45W 67.61'  
NE COR TURNER HEADSTONE S05E 46.50'

I-3:  
SET 5/8" x 36" REBAR IN MON BOX  
WEST LEG STOP SIGN POST S10E 51.10'  
EAST LEG STOP SIGN POST N25W 54.82'  
CENTER RISER N20E 89.44'  
SE CORNER STORAGE BLDG N60W 105.10'

SURVEY &  
REMONUMENTATION

MAY 16 1997

COMMISSION

Signed by *[Signature]*

Date 10 DECEMBER 1996

Surveyor's Michigan License No. PS#41093

