



LIBER 3 PAGE 124  
REMONUMENTATION

118391

RECORDED  
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'96 DEC 19 PM 2 20

For corners in

HILLSDALE

(County)

Located In:

Corner Code #

1. Public Land Survey	T	9S	R	3W	L-3, M-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Judy VanZandt  
REC. OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, JEFFREY BIESZK, in a field survey on 10 DECEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-3:  
1837 GLO  
POST  
16 W. OAK N39E 15 lks  
26 W. OAK S02E 22 lks

M-3:  
1837 GLO  
POST  
15 BEECH N18W 18 lks  
7 BEECH S53.5 W 16lks

SURVEY &  
REMONUMENTATION

MAY 16 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3: FOUND R.R. SPIKE 1 FOOT SOUTH CENTERLINE ROAD EAST AND WEST, 6.5 FEET EAST OF FENCE TO THE NORTH, 4 FEET WEST OF CENTERLINE OF ROAD TO THE SOUTH. MEASUREMENT FROM K-3 TO L-3 TO M-3 IS ON LINE AND IS A SPLIT OF THE MILE. ACCEPTED AS THE BEST AVAILABLE EVIDENCE TO THE POSITION OF THE CORNER.

M-3: FOUND NOTHING AT CORNER, EXTENDED K-3 AND L-3 TO IT INTERSECTED THE TOWNSHIP LINE. THE FALLING FROM A-3, T9S-R3W TO THE INTERSECTION WAS THE SAME AS THAT DONE BY GLO. ALSO MEASUREMENT FROM K-3 TO L-3 AND M-3 WAS A PERFECT SPLIT FOR THE MILE. ACCEPTED AS THE BEST AVAILABLE EVIDENCE TO THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3:  
SET 5/8" x 36" REBAR IN MON BOX  
CENTER RISER N45E 35.50'  
STOP SIGN POST S30E 51.50'  
ROAD SIGN POST S20W 51.87'  
NAIL & TAG FNC POST N15W 39.26'

M-3:  
SET 5/8" x 36" REBAR IN MON BOX  
CENTER RISER S25E 59.61'  
NAIL & TAG 8" ELM S55W 30.63'  
STOP SIGN POST N10E 70.70'  
NAIL & TAG NORTH POST TO SIGN FUNNY FARM CAMPGROUND  
N30W 57.92'



Signed by

*Jeffrey A. Bieszk*

Date 10 DECEMBER 1996

Surveyor's Michigan License No. PS 41093