

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 338

For corners in BUNKERHILL TOWNSHIP

INGHAM COUNTY

Located In:

Corner Code #

1. Public Land Survey	T <u>1</u> N R <u>1</u> E	C-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

980049403
09/29/1998 10:51:38
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on July 28, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original corner set by Joseph Wampler Deputy Surveyor on February 8, 1826 at a distance of 87.21 chains. "87.21 Intersect the township line 79 lks (52.14') West; B.O. 22 S 34 E 50; D. O. 9 S 7 W 32".
- Additional notes to Wampler's (different handwriting) show witnesses: Map 8 S 78 1/2 E 85 lks; Map 8 S 21 E 99 lks.
- LCRC recorded in Liber 4, Page 49 on April 29, 1977 by George M. Young RLS #17640. Monumentation described as "Set Iron record distance from SW Corner Section 32, T2N, R1E." Witnesses: #16 Nail in Telephone Pole N 45° W 38.30'; #16 Nail in 12" Maple N 85° W 44.25 feet; #16 Nail in 36" Maple S 50° E 51.36'.
- An Act 132 survey recorded in Liber 2, Page 1133 on May 25, 1977 by Austin C. Williams RLS #21275. Monumentation not mentioned; witness reference to Liber 4, Page 49 (same as in #3).

(Continued On Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron with orange cap (ID# destroyed) ±1.5' East centerline Meridian Road on fence line to West and on tree line to East extended. Found no witnesses; most obliterated. Excavated a 2' x 2' x 3' area and found nothing. Accepted position of 1/2" iron rod as best location for obliterated corner. Replaced 1/2" iron with 3/4" iron and aluminum cap P.A. 345 #28414 and set monument box around.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" iron and destroyed cap. Replaced with 3/4" iron and aluminum cap P.A. 345 #28414. Witnessed by:
3/4" bar and aluminum P.A. 345 cap #28414 (C-13 Ingham Twp., T2N, R1E) East 52.15'
Nail and Tag #28414 Southwest side 24" Maple S 50° E 51.87'
Nail and Tag #28414 North side 20" Cherry N 85° W 44.52'
Nail and Tag #28414 Southeast side 12" Pine N 30° E 148.48'

Signed by Maurice H. Mahieu

Date 9/22/98

Surveyor's Michigan License No. 28414



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1978

REVISED JAN., 1983
REVISED OCT., 1995

P.A. 345 INGHAM COUNTY
PEER APPROVED 9/22/98 ML

A. (CONTINUED)

- 5. An Act 132 survey recorded in Liber 7, Page 912 on October 9, 1996 by Ronnie M. Lester PS #18998. Monumentation described as "Found 1/2" bar 1.5' East centerline Meridian Road on centerline of drive to East to House #2515, "Witnesses: Set galvanized nail and 1 1/4" brass tag stamped "18998 Lester" NW side 30" Maple Mag. Az. 125°, 52.04"; Set galvanized Nail and 1 1/4" brass tag stamped "#18998 Lester" South side 18" Cherry Mag. Az. 281°, 44.59"; Set galvanized Nail and 1 1/4" brass tag stamped "#18998 Lester" West side Utility Pole Mag. Az. 173°, 112.78"; Bolt head in gravel, Mag. Az. 96°, 50.03'.

SLYNN &
REINCK'S SURVEYING

DEC 17 1998

SECTION

Recpt. No	97035
CH&R	9.00
MSSR	2.00
Total	11.00