

SURVEY & REMONUMENTATION

LIBER 8 PAGE 307

FILED

Nov 22 11 47 AM '94

For corners in
INGHAM
(County)

APR 10 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
BUNKER HILL

COMMISSION

Located In: Corner Code = 11

REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MICH.

- | | | | | | |
|------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | IN | R | IE | C-8 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Sec. | S | T | R | | |
| | S | T | R | | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Maurice H. Mahieu October 28 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. Original GLO survey done by J. Wampler between Jan. 30 and Feb. 6, 1826. Set 1/2 mile post at a distance of 40 chains. Witnessed by:
16" W.O., N 50 1/2" E, 19 1/2 links
18" W.O., S 38 1/2 deg. E 29 links

(Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Discussion with property owner revealed that iron, rocks and fence lines were taken out to clear fence row. Owner owns all land surrounding corner. No previous information dating back to original GLO survey indicates the origin of any corner set or reason for the 1/2" rod found by R. Keller. This surveyor determined that this corner is lost. Set 3/4" x 24" iron rod with cap PA 345, P.S.# 28414 by single proportionate measurement between C-7 and C-9. Set rod 3 ft. below grade due to location of corner is in a open plowed field. Measured North 2629.37' to C-7; South 2629.37' to C-9, East 5265.29 to E-8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 3/4" x 24" Iron Rod with cap "P.A. 345 #28414" Witnessed by:
C-7 NW Corner, Section 20, T1N, R1E, N 00 deg. 18' 47" E, 2629.37'
C-9 SW Corner, Sec. 20, T1N, R1E, S 00 deg. 18' 47" W, 2629.37'
D-8 Center of Section 20, T1N, R1E, S 89 deg. 54' 34" E, 2637.91'
BH1-15-17, 1/2" iron rod, N 80 deg. 41' 27" E, 1316.58'



Signed by *Maurice H. Mahieu* Date 11-14-94

Surveyor's Michigan License No. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1977
REVISED MAY 14, 1977
REVISED JAN., 1988

P.A. 345 INGHAM COUNTY
PEER APPROVED 11/9/94 *W*

A. (Continued)

2. LCRC Liber 6, Page 64, on June 3, 1980. Ronald W. Keller, PS #20707. Found 1/2" Re-bar in pile of rocks in line with fence East-West and 10", south of lane East-West witnessed by:
S 10" Elm 4.10"
N 87 deg. E Twin W.Cherry 61.88'
N 89 deg. W 20" Oak 95.77'
W 6" Fence Post 6.50'