

SURVEY & REMONUMENTATION COMMISSION

APR 10 1995

FILED

Nov 22 11 47 AM '94

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 BUNKER HILL

REGISTER OF DEEDS
Russell DeKoson
 INGHAM COUNTY, MICH.

For corners in
INGHAM
 (County)

Located In: Corner Code #/

- | | | | | | | |
|------------------------------------|---|-----------|---|-----------|-----|------------|
| 1. Public Land Survey | T | <u>1N</u> | R | <u>1E</u> | --- | <u>D-7</u> |
| | T | --- | R | --- | --- | --- |
| | T | --- | R | --- | --- | --- |
| | T | --- | R | --- | --- | --- |
| 2. Property Controlling in Section | S | --- | T | --- | R | --- |
| | S | --- | T | --- | R | --- |
| 3. Miscellaneous Property in Sec. | S | --- | T | --- | R | --- |
| | S | --- | T | --- | R | --- |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7		●											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Maurice H. Mahieu, in a field survey on October 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original GLO survey done by Joseph Wampler between January 30 and February 6, 1826. Set 1/4 Post at average of 40.15 chains, witnessed by:
 16" W.O. N 5 1/2° W, 56 links 36.96'
 8" W.O. N 64° W 33 links 21.78'
- Corner noted in survey done by A. Jackson, County Surveyor, November 28, 1845 (L-1, P-79). Witnesses same as in GLO survey.

(Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" pipe at base of fence post with ring of stone 4'Ø. Fence runs West & North. Tree line South. Removed 1/2" pipe and set 3/4" x 24" Iron Rod with Cap #28414, P.A. 345 at position of 1/2" pipe. Measured West 2,638.01' to C-7, South 5,245.08' to D-9. Accepted pipe as position of corner, based on occupation of fences North & South & West, and no other evidence to dispute location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" Rod w/Cap P.A. 345, P.S. 28414, witnessed by:
 Nail and Tag #28414 East Side 36" Oak, South 10.35'
 Nail and Tag #28414 North Side 10" Oak, S 50° W 5.85'
 Nail and Tag #28414 East Side Shag Bark Hickory, N 05° W 13.50'
 Nail and Tag #28414 Southeast Side 15" Ash, N 10° E 8.75'



Signed by Maurice H. Mahieu
 Surveyor's Michigan License No. #28414

Date 11-14-94

2706

- A. (Continued)
- 3. No other information found for corner.