

**SURVEY & REMONUMENTATION**  
**APR 10 1995**  
**COMMISSION**

FILED

Nov 22 11 48 AM '94

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**BUNKER HILL**

REGISTER OF DEEDS  
*Frank J. ...*  
 INGHAM COUNTY, MICH.

For corners in INGHAM (County) Located In: Corner Code #/1

1. Public Land Survey	T IN R IE	D-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9		●											
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **Maurice H. Mahieu**, in a field survey on **October 28**, 19**94**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Original GLO notes done by J. Wampler between January 30 and February 6, 1826. Set 1/4 post at an average distance of 40.12 chains. Witnessed by:  
 20" Elm N 30 1/2 deg. W 116 links  
 21" Ash N 79 deg. W. 139 links

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No recorded evidence of location could be found from the time of the original GLO corner. This surveyor determined this corner to be lost. Set 3/4" x 24" iron rod with cap PA 345, PS 28414 by single proportionate measurement between C-9 and E-9. Measured west 2637.80 feet; East 2637.80 feet North 5245.08 to D-7. Corner falls 8.5' South of East-West fence line in low wet area. Set three large stones and metal fence post adjacent to iron rod.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 3/4" x 24" Iron Rod with cap "P.A. 345 #28414" Witnessed by:  
 Nail and Tag #28414 S. side 54" Maple, West, 18.46'  
 Nail and Tag #28414 W side 10" Elm, S 20 deg. E. 5.10'  
 Nail and Tag #28414 E. side 20" Maple, S 20 deg. W, 30.60'  
 Nail and Tag #28414 E. side 10" Ash, S 22 deg. W 27.38'



Signed by Maurice H. Mahieu Date 11-14-94  
 Surveyor's Michigan License No. #28414