

SURVEY & REMONUMENTATION

LIBER 8 PAGE 317

FILED

Nov 22 11 48 AM '94

APR 10 1995
For corners in
INGHAM COMMISSION
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
BUNKER HILL

REGISTER OF DEEDS
Paul J. Johnson
INGHAM COUNTY, MICH.

	Located In:	Corner Code #/1
1. Public Land Survey	T 1 N R 1 E	E-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, Maurice H. Mahieu, in a field survey on June 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1. Original GLO survey done by Joseph Wampler, Government Surveyor, between January 30th and February 8, 1926. "Set 1/2 mile post at North end of Marsh". Witnessed by:
W.O. 18" N 24° W 118

2. A. Jackson, County Surveyor, indicated corner in survey dated November 23, 1841 (L-1, P-114). Witnessed by W.O. 18" N 24° W 118 links and 8" Oak N 54° E, 146 links..

(Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 5/8" iron rod surrounded by stones in North-South fence line (laying down). Found 4 of Ronnie Lester witnesses from A-3. Accepted position of 5/8" iron rod as corner. Replaced 5/8" iron rod with 3/4" x 24" iron rod with cap P.A. 345, P.S. #28414. This surveyor ^{accepted} corner position based on previous research I Ronnie Lester, P.S. and no other evidence to dispute location of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" x 24" Iron Rod Witnessed By:
Nail and Tag #18998 Northeast Side 40" Oak, N 75° W 35.65'
Nail and Tag #18998 Northeast Side 36" Oak, N 65° W 18.23'
Nail and Tag #18998 Northwest Side 18" Oak, N 55° E 22.88'
Nail and Tag #18998 Northwest side Twin 20" Oak, N 40° E 37.43'



Signed by Maurice H. Mahieu
Surveyor's Michigan License No. #28414

Date 11-9-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 1988, REVISED MAY 1993

(Continued)

Recorded and re-monumented by Ronnie M. Lester, Land Surveyor #18998, in Act 74 L.C.R.C. dated July 24, 1990 (L-7, P-186). Lester quoted "Investigation at this location revealed a 5/8" rebar in circle of stones in North-South fence line on woodline to West. G. Fauser, L.S., indicated he set this corner. Accepted rebar as perpetuated location of section corner. Measured North 2622.7', South 2640.3' and East 2655.5'.

Witnessed by:

5/8" Re-bar P5 - 04 - 23-E8 A - 4165

Nail and Tag Northeast side 36" Oak, 297° Az, 18.4'

Nail and Tag North side 40" Oak, 284° Az, 35.7'

Nail and Tag Northwest side 12" Red Oak, 54° Az, 22.9'

Nail and Tag Northwest side 24" Red Oak, 37° Az, 37.2'

Referred to in July 1990 Act 132 survey (L-6, P-312) by Ronnie Lester P.S. #18998 with same monumentation and witnesses as A-3.