

SURVEY & REMONUMENTATION

LIBER 8 PAGE 319

FILED

Nov 22 11 48 AM '94

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
BUNKER HILL

REGISTER OF DEEDS
Frank D. Larson
 INGHAM COUNTY, MICH.

For corners in INGHAM
 (County)

APR 10 1995

COMMISSION

Located In:

Corner Code: //

- 1. Public Land Survey T IN-- R 1E-- E-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Maurice H. Mahieu In a field survey on June 21, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Original GLO survey done by Joseph Wampler between January 30 and February 8, 1826. "Set a post at a distance of 80.00 chains" distance of 80 chains, witnessed by:
 11" Tamarack S 51° W 86
 12" Tamarack S 40 1/2° E 213
- 2. T. J. Brown utilized corner February 10, 1848 in survey by county surveyor. No Witnesses given. Liber 3, Page 178, Ingham County Surveyors Records.

B. Description of corner evidence found and/or method applied in restoring ^(Over) or reestablishing corner:

Found 1" x 24" iron bar in North-South-East and West fence line, area is low and wet, corner falls 22 feet West of centerline of North running drain and 10 feet South of East running drain. Found 4 of Ron Lester's witnesses A-3. Accepted 1" iron bar as position of corner, based on work performed by Ron Lester and no other evidence to displace location of corner. Removed 1" bar and set 3/4" x 24" smooth bar with cap P.A. 345 P.S. #28414.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" x 24" Iron Rod was left in position and witnessed by:
 Nail and Tag #18998 East Side 28" Maple, N 30° W 25.62'
 Nail and Tag #18998 Northeast Side Twin 12" Maples, S 70° W 31.02'
 Nail and Tag #18998 South Side 36" Maple, S 75° E 45.73'
 Nail and Tag #18998 North Side 28" Maple, S 20° W 43.09'
 Found 1/2" iron rod N 65° E 23.57 feet w/Lath #P5 07-30



Signed by Maurice H. Mahieu
 Surveyor's Michigan License No. #28414

Date 11-9-94

(Continued)

Recorded and remonumented in July 24, 1990, Field Survey by Ronnie M. Lester, Land Surveyor (L-7, P-186). Investigation of corner revealed old North-South fence line West of North-South ditch line. Set 1" x 24" steel bar. Prorated old distances between E-8 and E-10 on old North-South fence line. Corner falls 12' West of centerline of North ditch and 10' South of centerline of ditch to East. Measured North 2640.2', South 2640.2', East 2644.3'. Witnessed by:

1" x 24" Steel bar 55 A-4165

Nail & Tag in Blaze, East side 24" Soft Maple, 332° Az, 25.6'

Nail & Tag in Blaze, Northeast side Twin 12" Soft Maple, 252° Az, 31.0'

Nail & Tag in Blaze, North side 20" Soft Maple, 200° Az, 43.1'

Nail & Tag in Blaze, Southwest side 24" Soft Maple, 113° Az, 45.8'

Corner referred to in July 1990 Act 132 survey (L-6, P-312) by Ronnie Lester P.S. #18998 with same witnesses as A-3.