



## A. (Continued)

3. Corner referred to as a pointed stone with iron and brick.  
 36" Oak 28.4 NE  
 27" Oak 60.0 NNE  
 12" Elm 39.4 SW  
 4" Elm 67.3 NNW  
 Ingham County Road Commission Records (1969)
4. Corner re-established as an iron set in MDSH&T Government Monument Witness Form 280, September 14, 1968. Iron witnessed by:  
 30" Oak NNE 65.07'  
 36" Oak ENE 28.10'  
 10" Box Elder SW 90.18'  
 12" Wild Cherry NW 31.39'  
 Information on card notes Stephens Engineering.
5. Corner referred to as a 3/4" pipe in Ingham County Road Commission revised grid map 1972.  
 28" Oak NNE 64.69'  
 36" Oak East 27.97'  
 6" B. Elder SSW 68.40'  
 14" Cherry NW 31.15'
6. Corner recorded by Ronnie M. Lester, P.S. 18998, Land Surveyor, September 17, 1979 Act 74 Corner Remonumentation. (L-5, P-314) as part of Ingham County 1979 Remonumentation Project. Ronnie Lester states "Excavated a hold 10' x 10' to an average depth of 3.1' on the centerline of Williams Road and on a Tree/Fence line to the East and West. Found 3/4" pipe at road surface on the centerline of Williams Road and 2'± North of Tree/Fence line. Found pointed stone 0.7' below road surface on the centerline of Williams Road on a Tree/Fence line. Accepted pointed stone for corner....."  
 Set 4" x 36" Concrete Monument with 1/2" x 38" rerod and cap #18998 with concrete collar and cover in location of pointed stone:  
 Nail and Tag #18998 South side of 36" Oak, East 27.64'  
 Nail and Tag #18998 East side of 12" Cherry, NW 32.99'  
 Nail and Tag #18998 NW side 32" Oak, NE 68.45'  
 Nail and Tag #18998 East side 24" Oak, NNW 131.38'
7. Corner referred to in survey by George M. Young, August 24, 1982, (L-4, P-585) as found 1/2" iron in monument box, witnessed by:  
 Found Nail and Tag 36" Oak, East 27.64'  
 Found Nail and Tag 18" Cherry, NW 32.99'  
 Found Nail and Tag 32" Oak, NE 68.45'
8. Corner referred to in Act 132 survey by Ronnie M. Lester, July 1990 (L-6, P-512) as a Concrete Monument in monument box as recorded in Liber 5, Page 314, witnessed by:  
 Found Nail and Tag #18998 in South side 45' Oak, 90° Az 27.6'  
 Set Nail and Tag in Northwest side 36" Oak, 21° Az 68.7'  
 Found Nail and Tag in Northeast side 18" Cherry, 322° Az 32.9'  
 Found Nail and Tag #18998 in East side 24" Oak, 353° Az 131.3'
9. Corner referred to in Act 132 survey by Ron Helsel P.S. #18994, July 31, 1992 (L-6, P-1162) with same witnesses as A-6.