

**SURVEY & REMONUMENTATION**

APR 10 1995

COMMISSION

Nov 22 11 48 AM '94

REGISTER OF DEEDS  
*Russ Johnson*  
 INGHAM COUNTY, MICH.

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
**BUNKER HILL**

For corners in  
INGHAM  
 (County)

Located In:

Corner Code: 11

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>1N</u> - R <u>1E</u> | <u>F-8</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous                   | S _____ T _____ R _____   | _____      |
| Property in Sec.                   | S _____ T _____ R _____   | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Maurice H. Mahieu, in a field survey on June 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1. A corner was not set in original government survey.

2. A. Jackson, County Surveyor, called for corner in survey dated November 23, 1841. Witnessed By:  
 5" Poplar S 35° E 12 links  
 4" W.O. S 34° W 49 1/2 links

(Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

With visible inspection of monument, found 1/2" Iron Rod with cap #18998. Corner falls 3'± East of centerline of Williams Road and 105'± South of centerline of Battcese Creek. Found 4 of Ronnie Lester's witnesses from A-4. This surveyor accepts corner based on previous work by R. Lester.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The found 1/2" iron rod with cap #18998 was left in place and witnessed by:  
 Nail and Tag #28414 North Side 28" Cherry, S 58° E 26.22'  
 Nail and Tag #28414 North Side 42" Walnut, S 83° W 29.44'  
 Nail and Tag #28414 North Side, 20" Cherry, N 81° E 21.66'  
 Nail and Tag #28414 East Side 20" Walnut, N 35° W 49.92'



Signed by Maurice H. Mahieu  
 Surveyor's Michigan License No. #28414

Date 11-14-94

## A. (Continued)

3. Ingham County Remonumentation Program of 1979 did not excavate for this corner. Marginal notes on inside cover of file states "visual recon unsuccessful - to be determined by distances. Corner lost RL 5/15/79 "No indication of excavation was stated in the file.
4. Referred to in Act 74 L.C.R.C. by Ronnie M. Lester, July 24, 1990 (L-7, P-188).  
Set 1/2" bar and cap at intersection of North-South and East-West 1/4 lines.  
Measured North 2617.7' (Jackson 2616.9'), East 2665.7' (Jackson 2628.8'),  
West 2655.5' (Jackson 2626.8') measured South 2650.8'.  
Corner falls 105' South of centerline of East-West drain and 3' East of centerline of Willams Road. Witnessed By:  
Nail and Tag North Side of 30" Walnut, 263° Az, 28.5'  
Nail and Tag East Side of 18" Walnut, 327° Az, 50.0'  
Nail and Tag East Side of 18" Walnut, 200° Az, 107.8'  
Nail and Tag North Side of 18" Cherry, 85° Az, 21.7'
5. Referred to in survey by Ronnie M. Lester, July 1990 (L-6, P-312) with same witnesses as A-4.