

SURVEY & REMONUMENTATION

Nov 22 11 48 AM '94

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
BUNKER HILL

For corners in INGHAM
(County)

Located In: _____ Corner Code #F-9

REGISTER OF DEEDS
Paul Johnson
INGHAM COUNTY, MICH.

- 1. Public Land Survey T IN— R 1E— — F-9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Maurice H. Mahieu, in a field survey on June 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1. Original G.L.O survey done by Joseph Wampler between January 30th and February 8, 1826.
Set 1/4 Post "at average distance 40.07 chains" witnessed by:
W.O. 18" S 23° W 90
B.O. 12" S 61° W 82
 - 2. George Young, Land Surveyor, Act 132 survey (L-4, P-585) dated August 24, 1982 called for 3/4" pipe with witnesses: Nail and Tag SE 2.25 6" Oak
Nail and Tag NW 8.10 24" Oak
Nail and Tag SW 18 75" Hickory (Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rebar in East and West fence line, in small rock pile. Found all 4 of Ronnie Lester's witnesses per A-4. Accepted position of 5/8" rebar as perpetuated corner and replaced with 3/4" x 24" iron bar and cap P.A. 345, P.S. #28414. Corner falls 138 feet East of the centerline of Williams Road. This surveyor accepts the location of the 3/4" rod based on there is no other occupation or location to refute this location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The 3/4" rod w/cap P.A. 345, P.S. #28414 is witnessed by:
Nail and Tag #28414 East Side 20" Oak, North 34.50'
Nail and Tag #28414 East Side 15" Oak, N 17° W 19.05'
Nail and Tag #28414 North Side, 36" Oak, S 85° W 15.56'
Nail and Tag #28414 East Side 18" Oak, S 65° W 17.56'



Signed by Maurice H. Mahieu Date 11-9-94
Surveyor's Michigan License No. #28414

62
A. (Continued)

B. G. Fauser, Land Surveyor, P.S. #18657 unrecorded survey, indicating establishment of corner in survey dated July 1988. Fauser 5/8" re-bar found in old East-West fence line on extension of road to North in apparent old fence intersection.

4. Referred to in Act 74 Land Corner Recordation Certificate by Ronnie M. Lester, Land Surveyor #18998, July 24, 1990 (L-7, P-188). Accepted 5/8" re-bar set by Fauser. Measured West 2644.4', North 2650.8', and Fauser indicates 2638.0' East.

G. Young corner falls 92' East and 36' North of this corner.

Witnessed By:

Nail and Tag South Side of 36" Basswood, 27° Az 15.5'

Nail and Tag East Side of 12" Oak, 343° Az, 19.0'

Nail and Tag North Side of 36" Oak, 265° Az, 15.6'

Nail and Tag East Side of 15" Oak, 245° Az, 17.6'

G. Young pipe and cap 72° Az, 98.6'

5. Referred to in survey by Ronnie M. Lester, July 1990 (L-2, P-312) with same witnesses as A-4.