

Nov 22 11 48 AM '94

REGISTER OF DEEDS
TNGHAM COUNTY, MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION
APR 10 1995
INGHAM COUNTY COMMISSION

Located In: _____ Corner Code #/1 _____

1. Public Land Survey T IN R IE G-7
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Maurice H. Mahieu in a field survey on October 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1. Original GLO Survey done by Joseph Wampler between January 30 and February 8, 1826. Set corner post at a distance of 80.00 chains, witnessed by:
 18" B.O. South 7 links; 10" B.O. N 96 deg. W 50 links

Ingham County Road Commission Revised Grid Map

2. Brick, stone, crockery witnessed by: 18" Maple 23.6' WSW
 12" Oak 59.3' NNW on West fence line
 21.1' to Anchor Post (Over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Railroad Spike as called for in A-3. Found witnesses as noted in A-3. Removed railroad spike and dug down 3'+/-. Found pointed stone with brick surrounding stone 2.6 feet below road surface. Stone is 2.1 feet North of Railroad Spike. Left stone in position and placed a 3/4" x 24" iron rod with cap #28414, P.A. 34 over pointed stone. Set monument box over 3/4" rod. 3/4" iron is 10.2' West of painted centerline of Williamston Road and on projected centerlines of Williamston Roads which runs North and Southeast. The location of the stone with the 3/4" iron rod is the perpetuation of the corner as determined by this surveyor based on past local survey history indicates similar stones and brick used for section corners. Did not reset railroad spike.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 3/4" Iron Rod with cap P.A. 345, P.S. #28414, Witnessed by:
 Nail and Tag #28414 North side 36" Maple, S 89 deg. W 22.80'
 Nail and Tag #28414 East side Utility Pole, S 10 deg. W 200.75'
 Nail and Tag #28414 North side Fence Post, East 30.90'
 Nail and Tag #28414 Top of 38" Oak Stump, East 55.50'
 Nail and Tag #28414 East side 36" Oak, N 20 deg. W 59.00'



Signed by Maurice H. Mahieu Date 11-14-94
 Surveyor's Michigan License No. 2715 #28414

A. (Continued)

3. Corner recorded July 24, 1973 by Charles C. Wilson, Land Surveyor in L.C.R.C. (L-2, P-555).
Found Railroad Spike, Witnessed by:
38" Sugar Maple, S 84 deg. W 22.45' to Nail
28" R. Oak, N 26 deg. W 61.22' to Nail
38" W. Oak, S 89 deg. E 54.40' to Nail
26" Swamp W. Oak, N 42 deg. W 36.53' to Nail
4. Act 132 Survey recorded November 25, 1973 referring to corner and railroad spike (L-1, P-1032)
by Charles C. Wilson, P.S. #13604.