

SURVEY & REMONUMENTATION

APR 10 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
BUNKER HILL

LIBER 8 PAGE 329

FILED

Nov 22 11 49 AM '94

REGISTER OF DEEDS
Paul Johnson
 INGHAM COUNTY, MICH.

For corners in INGHAM Located In: _____ Corner Code 77
(County)

- 1. Public Land Survey T IN R 1E G-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on June 21 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	5	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Original GLO survey done by J. Wampler between January 30 and February 6, 1826. Set 1/2 mile post at a distance of 40 chains. Witnessed by: B.O. 18" South 7 deg.; B.O. 10" N 46 deg. W 50 links.
- 2. Survey done by A. Jackson, County Surveyor, Nov. 23, 1841 (L-1, p.114) called for corner. Same witnesses as GLO.
- 3. County Survey done September 3, 1888, called for corner witnessed by: 12" Cherry N 84 deg. W 43 links; 10" Cherry N 35 deg. 104 links. No surveyors name given.
- 4. Unrecorded survey by Glen Fauser No 18657, dated Dec. 10, 1988, shows corner but does not indicate monumentation or witnesses.

B. Description of corner evidence found and/or method ^(Over) applied in restoring or reestablishing corner:

Found 1/2" rebar with cap #18657 on East side of large pointed stone surrounded by smaller stones. Found rotted wood post lying north 2' ± of 1/2" rebar. An East and West fence line runs through corner location. Found 4 of Ron Lester's witnesses as per A-5. Replaced 1/2" rebar and cap #18657 with 3/4" iron rod and cap PA 345, PS #28414 (Standard Monumentation). This survey accepts corner based on previous work by Fauser and Lester. Also accepts based on stones found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" Iron Rod with cap "P.A. 345 #28414" Witnessed by:
 Nail and Tag #18998 N. side Twin 18" Cherry, East 5.94 feet
 Nail and Tag #18998 S. side Twin 12" Cherry, N 65 deg. E 27.39 feet
 Nail and Tag #18998 S. side 20" Cherry, west 10.19 feet
 Nail and Tag #18998 W. side 12" Crab Apple N 15 deg. W 34.03 feet



Signed by Maurice H. Mahieu Date 11-9-94
 Surveyor's Michigan License No. #28414

Corner Recordation Certificate dated July 13, 1990 by Ronnie M. Lester, Land Surveyor, (L-7, P-187). Found 1/2" bar and cap #18657 in old East-West fence line in circle of stones. Measured West 5321.21' and G.Fauser #18657 indicates 2641.2' South. Accepted by perpetuated location of original corner. Witnessed by:
Nail & Tag South side 10" Twin Cherry, 64 deg. 92, 27.5'
Nail & Tag North side 15" Twin Cherry, 102 deg. 92, 6.0'
Nail & Tag West side 10" Crab Apple, 344 deg. 92, 34.0'
Nail & Tag South side 18" Cherry, 270 deg. 92, 10.2'

Corner referred to in July 1990 survey (L-6, p-311) by Ronnie M. Lester #18998 with same witnesses as A-5.