

SURVEY & REMONUMENTATION

APR 10 1995

COMMISSION

LIBER 8 PAGE 331

FILED

Nov 22 11 49 AM '94

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
BUNKER HILL

REGISTER OF DEEDS
Ingham County, Mich.

For corners in INGHAM (County)

Located In: Corner Code #/

- 1. Public Land Survey T IN - R IE - G-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Maurice H. Mahieu, in a field survey on September 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Original GLO survey done by J. Wampler between January 30 and February 6, 1826. Set a post at a distance of 80.00 chains. Witnessed by: 26" Elm N 28 1/2 deg. E 49 1/2 links' 13" Elm N 38 1/2 deg. E. 59 links
2. Survey done by A. Jackson, County Surveyors, Nov. 23, 1841 (L-1, p.114). Witnesses same as GLO survey.
3. Unrecorded survey by Glen Fauser PS #18657, dated Dec. 10, 1988 states "Set 1/2" x 18" capped rebar, 60" W, Oak W 75.2' to N&W W. side; 26" Maple N 80 deg. W 10.3' to N&W on S. side. Corner is on top of S. Ditch Bank; C/L E/W Ditch in 10'; E&W fence S 1.5' measures 2650.13 to H-9; 2641.20 to G-8. Field notes by Fauser indicates 2638.01 to F-9.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod and cap #18657 (Glen Fauser) at East side of 6" diameter stone. Stone and iron falls in downed East-West fence line and 3'± South of South bank of East-West ditch. Replaced 1/2" rod with 3/4" x 24" iron rod with cap P.A. 345, PS #28414. This surveyor accepts the location of 1/2" iron rod as position of corner based on no other evidence to dispute location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" Iron Rod with cap "P.A. 345 #28414" Witnessed by:
Nail and Tag #28414 S. side 36" Basswood, n 75 deg. W 10.02 feet
Nail and Tag #28414 W side 8" Cherry, South 10.15 feet
Nail and Tag #28414 W side Oak Clump, S 45 deg. E 13.10 feet
Nail and Tag #28414 N side Oak Clump, S 75 deg. E 24.22 feet



Signed by [Signature] Date 11-14-94
Surveyor's Michigan License No. #28414

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

P.A. 345 INGHAM COUNTY
PREFR APPROVED 11/9/94 M

2717