

SURVEY &  
REMONUMENTATION

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 370

For corners in

INGHAM

Located In:

Corner Code #

(County)

BUNKERHILL /TWP.

1. Public Land Survey

T 1 N R 1E L-2

T     R        

T     R        

T     R        

2. Property Controlling  
in Section

S     T     R        

S     T     R        

3. Miscellaneous  
Property in Sec.

S     T     R        

S     T     R        

FILED

980053103  
10/19/1998 13:55:00  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DAVID R. LOHR, PS, in a field survey on 9/21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-2: 1. CORNER NOT SET IN G.L.O. SURVEY.

2. CORNER REFERENCED IN SURVEY BY A. JACKSON, CO. SURVEYOR, DATED NOV. 20, 1841, RECORDED IN OLD VOL. 1, PG.113). NO MENTION OF MONUMENT. WITNESSED BY: W.O: 18" N 32 E 35 1/2 LKS (23.43')  
" 16" N 32 1/2 W 5 LKS (3.30')

NOTES SHOW DISTANCE SOUTH TO 1/8 COR. OF 80 R, 2L. (1321.32')

NOTES SHOW DISTANCE EAST TO M-2 OF 162 R, 16 L. (2683.56')

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-2: SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND BOSS'S P.K. NAIL AS PER ITEM #7-PART A. CORNER FALLS ALONG FENCELINE EAST AND WEST AND APPROXIMATELY MIDWAY BETWEEN REMAINS OF ANCIENT ANCHOR POST LOCATIONS. EXCAVATED AN AREA 2 FT. X 2 FT. THRU TWO LAYERS OF BIT. TOTALING 8" IN DEPTH. AT DEPTH OF 36" FOUND TOPSOIL. AT 40" DEEP FOUND TOP OF STONE WITH BITS OF ANCIENT WOOD. STONE MEASURES 8" X 8" X 15" LONG AND IS LYING ON ITS SIDE TO THE NORTHWEST. LOCATION OF P.K NAIL FALLS ALONG THE CONTINUED ON BACK

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-2: SET STANDARD 3/4" X 24" REMON. BAR AND 2" ALUMINUM PA#345 CAP #30090 ALONG EAST SIDE OF STONE, AT LOCATION OF BOSS'S PK NAIL. WITNESSED BY:  
SET N&T #30090, NE/S 10" BASSWOOD, N 59 W, 36.18'  
SET N&T #30090, NW/S TW. 15" OAK, N 52 E, 42.53'  
SET N&T #30090, N/S 20" SHAG-BARK, S 85 E, 26.22'  
SET N&T #30090, SW/S 10" OAK, S 47 E, 33.70'  
TRAVERSE PT. BH1-39-141(1/2" IRON) S 08 E, 76.62'

Signed by David R. Lohr  
Surveyor's Michigan License No. 30090

Date 9-24-98



DEC 17 1998

SECTION

L-2: BUNKERHILL TOWNSHIP, PART A - CONTINUED

3. CORNER REFERENCED IN SURVEY BY A. JACKSON, CO. SURVEYOR, DATED MAY 20, 1843, RECORDED IN BOOK 4, PAGE 116. (OLD VOL. 1, PG. 117). NO MENTION OF MONUMENT. WITNESSED BY: SWP. OAK 14" S 58 W 13 LKS (8.58')  
" " 14" N 27 E 56 LKS (36.96')  
NOTES SHOW DISTANCE SOUTH TO L-3 OF 160 R, 14L. (2649.24')  
NOTES SHOW DISTANCE WEST TO 1/8 COR. OF 79 R, 18 L. (1315.38')
4. CORNER REFERENCED IN SURVEY BY A.P. DRAKE, COUNTY SURVEYOR, DATED APRIL 16, 1880, RECORDED IN BOOK 3, PAGE 31, (OLD VOL.3, PG. 172). "A STONE. CORNER LOCATED BY A. JACKSON, MAY 20, 1843." NO WITNESSES GIVEN.  
SURVEY SHOWS DISTANCE NORTH TO L-1 OF 42.97 CH. (2836.02')  
SURVEY SHOWS DISTANCE NORTH TO 1/8 COR. OF 20.76 CH. (1370.16')  
SURVEY SHOWS DISTANCE EAST OF 40.66 CH. (2683.56')  
SURVEY SHOWS DISTANCE SOUTH TO 1/8 COR. OF 20.02 CH. (1321.32')
5. CORNER NOT REFERENCED ON INGHAM COUNTY GRID MAP, DATED JAN. 1969,
6. CORNER REFERENCED IN SURVEY #3634, BY OSCAR BOSS, RLS #13574, DATED 02/21/73, RECORDED IN LIBER 1, PAGE 810. "CENTER, SEC. 1, TIN, RIE, P.K. NAIL SET." WITNESSED BY: N 46 E, 42.49', 10" HICKORY  
DUE EAST, 26.54', 12" HICKORY  
S 55 E, 63.50', 18" ASH  
SURVEY SHOWS DISTANCE NORTH TO L-1 OF 2833.02'
7. CORNER REFERENCED IN SURVEY #3823, BY OSCAR BOSS, RLS #13574, DATED 06/04/73, RECORDED IN LIBER 1, PAGE 835. "CENTER SECTION. P.K. NAIL SET." SAME WITNESSES AS ITEM #6. SURVEY SHOWS DISTANCE NORTH TO L-1 OF 2833.02'  
SURVEY SHOWS DISTANCE WEST TO K-2 OF 2634.15'
8. LCRC, BY OSCAR BOSS, RLS #13574, DATED 10/16/73, RECORDED IN LIBER 3, PAGE 107. "PART A: L-2: UNKNOWN.  
PART B: L-2 P.K. SET FENCE INTERSECTION & CENTERLINE BLACKTOP."  
PART C: SAME WITNESSES AS ITEM #6.
9. CORNER REFERENCED IN SURVEY #1720, BY AUSTIN C. WILLIAMS, RLS #21275, DATED 07/03/78, RECORDED IN LIBER 3, PAGE 484. "CENT. SEC. 1, TIN, RIE." SAME WITNESSES AS ITEM #6.  
SURVEY SHOWS DISTANCE WEST TO K-2 OF 2635.16'
10. SURVEY #240 BY MARVIN F. FOUTY, P.S. #18989, DATED 8/5/78, RECORDED IN LIBER 3, PAGE 556, STATES: "CENTER, SEC. 1, TIN, RIE, FND. P.K. NAIL FROM WITNESSES, TAGS IN:" SAME WITNESSES AS ITEM #6.  
SURVEY SHOWS DISTANCE EAST TO M-2 OF 2637.97'
11. NO OTHER REFERENCES FOUND.

L-2: BUNKERHILL, PART B: CONTINUED:

EAST SIDE OF THE STONE, IF IT WERE UPRIGHT. ACCEPTED STONE AS THAT NOTED BY DRAKE IN 1880. ACCEPTED P.K. NAIL AS FAITHFUL PERPETUATION OF CORNER AND REPLACED IT WITH STANDARD 3/4" X 24" REMON. BAR AND 2" ALUMINUM PA #345 CAP STAMPED #30090 IN MONUMENT BOX.