

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY 31 T. 1 N. R. 1 E. C-11, C-12, C-13
2. PROPERTY CONTROLLING IN SECTION 31 T. 1 N. R. 1 E. C-11, C-12, C-13
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S. R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, D. Scott do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on Sept. 27 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Sept. 27 1973, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11 Found patched 4' square hole in blacktop with 1/2" iron rod in center,
C-12 Found patched 4' square hole in blacktop with 1/2" iron rod in center,
C-13 Found Boat Spike 2" below surface. Replaced with 1"x30" iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-11 NE Corner Section 31, T1N, R1E East 30.00' Iron Axel, N88°W 31.00' Fence Corner Post, S26°W 77.88' 7" Black Oak, S25°E 50.84' 42" Black Oak, S78°E 50.36' 22" Black Oak
C-12 E 1/4 Corner Sec 31, T1N, R1E S 23°W 111.44' 28" Black Oak, N65°E 48.97' 4" Conc. Mon. U.S.G.S.B.M, N 52° E 43.46' 30" Maple, N31°W 50.57' 6" Shag Bark Hickory, N 32° W 35.82' Telephone Anchor Pole
C-13 SE Corner Section 31, T1N, R1E S 82°W 27.29' 24" Black Oak, S 67°E 29.71' 26" White Oak, S 20° E 62.11' 25" Black Oak, S35°W 47.73' 10" White Oak

SIGNED BY DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12029 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.